

2026 RS Means Cost Data			
Item	Unit	Notes:	Cost
Concrete Saw Cutting	Linear Foot	Equipment & labor	\$3.25
7" Residential Concrete	Square Yard	Hand formed & placed	\$54.50
8" Residential Concrete	Square Yard	Hand formed & placed	\$61.50
9" Residential Concrete	Square Yard	Hand formed & placed	\$70.00
7" Residential Concrete	Square Yard	Slip formed	\$51.00
8" Residential Concrete	Square Yard	Slip formed	\$58.00
9" Residential Concrete	Square Yard	Slip formed	\$66.00
10" Commercial Concrete	Square Yard	Slip formed, including joint reinforcement & sawcut. No CSB included	\$67.12
24" Concrete Curb	Lineal Foot	Hand formed and placed	\$37.50
24" Concrete Curb	Lineal Foot	Straight slip formed.(add 10' of hand placed curb for each Catch Basin)	\$13.95
24" Concrete Curb	Lineal Foot	Radius slip formed. (intersections and cul-de-sacs)	\$17.15
4" CSB for Commercial Concrete	Square Yard	CSB for commercial concrete street	\$21.05
Asphalt Hauling	Cubic Yard	Asphalt trucking	\$13.50
1.25"-1.5" Surface Asphalt	Square Yard	Surface asphalt material, hauling, and tack coat	\$26.49
Surface Asphalt	Ton	Material, Labor, and Equipment (Hauling not included)	\$128.00
4" Base Asphalt	Ton	Material, Labor, and Equipment (Hauling not included)	\$106.00
4" Base Asphalt	Square Yard	Base asphalt, Labor, Equipment, and Hauling	\$37.50
4" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$39.29
3.5" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$36.79
3" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$34.04
2.5" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$31.19
2" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$28.39
1.5" Binder Course	Square Yard	Intermediate asphalt course, hauling, and tack coat	\$25.49
14" Commercial Asphalt	Square Yard	Base asphalt (for placement over CSB Commercial)	\$96.79
12" Commercial Asphalt	Square Yard	Base asphalt (for placement over CSB & Geogrid Commercial)	\$88.29
7" Crushed Stone Base (CSB)	Square Yard	Base for asphalt with or without geogrid	\$25.63
Geogrid-4'x50' (Tensar TX5)	Square Foot	Optional for asphalt pavements	\$1.79
Edge Drain	Lineal Foot	Per Lineal Foot of Curb	\$2.49
Milling	Square Yard	1" to 3" deep	\$16.17
Joint Sealant	Lineal Foot	Horizontal and Transverse	\$4.87
Sidewalk, Concrete	Lineal Foot	4' wide 4" thick	\$60.00
Sidewalk, Concrete	Lineal Foot	5' wide 4" thick	\$42.50
Sidewalk, Asphalt	Lineal Foot	5' wide 5" thick.	\$45.30
Seed & Mulch	Square Yard	Under 1 acre to cover and hand spread	\$1.99
Seed & Mulch	MSF	Over 1 acre to cover and tractor spreader	\$134.00
14"-24" Pipe Cleaning	Lineal Foot	Cleaning Inside of storm pipe	\$10.21
Class II Rip Rap, not grouted	Square Yard	Square yard of material 18" thick	\$165.00
Subgrade Prep	Square Yard	Grading, compaction & water conditioning	\$3.86
Mobilization	%		10% of Sub-Total
Demobilization	%		5% of Sub-Total
Contingency	%		10% of Sub-Total